

BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineer

Yelahanka Division

B.B.M.P. Bengaluru - 64

No: EE/YNK/BBMP/E-PMT/03/2018-19 Dated: 01-12-2018

APPROVED TENDER SCHEDULE - 'B'


Item No: 06


Name of Work: Emergency works in ward no 04

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri. ANJAN KUMAR Y A	
				Rate	Rate in Words
1	Excavation and removal of silt or silt mixed with sand in slussy condition from canal bed including disposing off the same in spoil bank or on the canal embankment in layers as directed etc., complete with initial lead upto 50 m and all lifts. MISR 2014-15 Page No 131 item No 51	cum	864.00	138.00	Rupees One Hundred Thirty Eight Only
2	KSRRB 300-1, Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift up to 1.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no 19.1, Page no 143, PWD SR 2018-19)	cum	18.00	129.00	Rupees One Hundred Twenty Nine Only
3	KSRB 100-1 Loading and unloading of stone aggregates / sand / kanker / Moorum / soil KSRRB M100-1 Placing tipper at loading with front end loader dumping turning for return trip excluding time for hauled and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 cost of haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 136 (SR 2018-19)	cum	882.00	82.00	Rupees Eighty Two Only

Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri. ANJAN KUMAR Y A	
			Rate	Rate in Words
4 KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No.KBS 4.1, 4.2 (P.12/I.4.3)/ PWD SR 2018-19	Cum	9.30	5077.00	Rupees Five Thousand Seventy Seven Only
5 Providing and laying Plain /reinforced cement concrete for side drains wall and bottom thickness 15cm using M20 nominal mix concrete with OPC cement at 300kg with 20mm and down size granite metal coarse aggregate at 0.69 cum and fine aggregate at 0.43 cum machine mixed well compacted for walls at bottom including centring shuttering cost of materials HOM of machineries curing etc.completeexcluding cost of steel as per MORTH specification No.1500,1700,2200 Page No 271 Item No 37.59.2 SR 2018-19	Cum	20.40	6638.00	Rupees Six Thousand Six Hundred Thirty Eight Only
6 KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. TMT bars Fe 500 KBS 4.6.3 Page No. 18/ Item No. 4.46/ PWD SR 2018-19	Tonne	1.39	70628.00	Rupees Seventy Thousand Six Hundred Twenty Eight Only
7 RCC Precast covering slab for drain (10cm thick)	sqm	31.50	1971.60	Rupees One Thousand Nine Hundred Seventy One and Paise Sixty Only
8 Providing precast slab of 250 mm thick in	sqm	14.40	4798.75	Rupees Four Thousand Seven Hundred Ninety Eight and Paise Seventy Five Only

Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri. ANJAN KUMAR Y A	
			Rate	Rate in Words
9 Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x200x400 mm and finished with CM 1:3 plastering and finishing cutting etc., complete. Page No. 27/ Item No. 5.29/ PWD SR 2018-19	Nos	111	448.00	Rupees Four Hundred Forty Eight Only
10 Engaging on Hire Basis JCB including Driver/operator with fuel etc complete (SR 2018-19) Page No XLVIII code 1031) SI No 23	Day	2	5347.00	Rupees Five Thousand Three Hundred Forty Seven Only
11 Engaging on Hire basis of Tractor 50 HP for Conveying of excavated and removal of Stuff from work spot (SR 2018-19) Page No XLVIII code 1024) SI No 23	Day	30	2359.00	Rupees Two Thousand Three Hundred Fifty Nine Only
12 Labour charges to Unskilled Mazdoor Heavy (Page no .LIV)SR 2018-18 si No	Day	240	419.00	Rupees Four Hundred Nineteen Only


Signature of the Contractor


Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.